



THE HYDERABAD CRICKET ASSOCIATION

Rajiv Gandhi International Cricket Stadium, Uppal, Hyderabad – 500 039, A.P.

Email: hycricket@rediffmail.com.

BILL OF QUANTITIES (PRICE QUOTE)

Name of Work : providing wash room block at Gymkhana Grounds, Secunderabad.

S.No	Description of Item	Qty	Rate/ Unit	Amount
01	Earth work excavation for basement in ordinary soils by manual. Including cost and conveyance of all materials and labour etc complete for finished item of work.	127.50 Cft		
02	Plain cement concrete in (!:5:10) for foundations and under tile flooring using 40MM size hard machine crushed granite metal Including cost & conveyance of all materials, curing & labour charges etc for finished item of work.	104.70 Cft		
03	Coursed Rubble Stone masonry in CM (1:6) prop with 2nd sort using hard granite stones carted from approved quarry and 40mm for packing. including bond stone of 24 x 24 x 39 cm, labour for cutting stones to required size, shape and dressed, mixing of cement mortar, construction, curing etc., complete for finished item of work.	169.00 Cft		
04	Filling of excavated soil inside the basement including cost of labour etc complete for finished item of work.	171.00 Cft		
05	Brick masonry in CM (1:6) prop. With 230mm thick clay red bricks for outer wall. Including cost and conveyance of all materials, scaffolding and labour charges, curing etc. Complete for finished item of work.	442.00 Cft		
06	Reinforced brick masonry in CM (1:4) prop. With 100 mm thick of light weight clay bricks. Including scaffolding, cost and conveyance of all material and labour charges etc. Complete.	61.00 Sft		
07	Outer plastering 20 MM thick in two coats with base coat of 16MM thick in (1:5) prop. and sponge coat in (1:3) prop. Including scaffolding charges, cost & conveyance of all materials, curing etc complete for finished item of work.	783.00 Sft		
08	Internal Plastering 20 mm thick in single coat in CM (1:5) prop. including scaffolding, cost and conveyance of material and labour charges etc comp.	520.00 Sft		
09	Flooring with non-skid vitrified tiles of 1 st quality of size 600x600 mm over a base coat of CM (1:8) prop. , with neat cement slurry and jointed with white cement mixed with matching pigment. Including cost and conveyance of all material and labour charges etc. Complete for finished item of work.	253.00 Sft		


for THE HYDERABAD CRICKET ASSOCIATION

(IMTIAZ KHAN)
Interim-CEO

12/11/25



CONTRACTOR



THE HYDERABAD CRICKET ASSOCIATION

Rajiv Gandhi International Cricket Stadium, Uppal, Hyderabad – 500 039, A.P.

Email: hycricket@rediffmail.com.

10	Providing dadooing to walls with coloured glazed tiles of 1 st quality of size 300x600 mm size set over base coat of CM (1:5) prop. Jointing with white cement paste mixed with matching pigment including cost and conveyance of material and labour charges, curing etc. Complete for finished item of work.	280.00 Sft		
11	Supply and fixing of WPC doors fully panelled single shutters all fixtures. Including cost and conveyance of material and labour charges etc., Complete for finished item of work.	03 Nos.		
12	Supply and fixing of ventilators of size 450x600mm with readymade cement blocks. Including cost and conveyance of material and labour charges etc Complete.	04 Nos.		
13	Supply and fixing of 0.5mm thick blue colour sheets with 2 inch pipes and u bolts including cost and conveyance of all materials, transport and fixing labour charges etc., complete for finished item of work.	282.00 Sft		
14	Supply and fixing of black granite platform of size 7'0"x 2'6" for wash basins including brick work for supporting the granite only, Plastering the walls 2 coats and cutting for wash basin fitting. Including cost and conveyance of all materials and labour charges and double moulding for granite etc., complete for finished item of work.	01 Nos.		
15	Supply and fixing of 5 mm thick Modiguard make mirror with ornamental teak wood beading of size 2" x 1" all round the mirror and 6 mm thick plywood back with necessary fitting etc., including all charges etc. Complete for finished item of work.	15.00 Sft		
16	Dismantle the existing water tank wash area and rebuild the wash area with red brick masonry and 20mm single coat plastering and cladding with 200x300 glazed tiles. Including cost and conveyance of all materials and labour charges etc., complete for finished item of work.	Lumpsum		
17	Dismantle the tree platform and rebuild the same in round shape flooring with tandur flooring and side plastering 20mm thick in two coats. Including cost and conveyance of all materials and labour charges etc., complete for finished item of work.	Lumpsum		
Total Amount Excluding Taxes				

for THE HYDERABAD CRICKET ASSOCIATION

(IMTIAZ KHAN)
Interim-CEO

10/11/25



CONTRACTOR

09/15/10/25

Gymkhana ground toilet

